

# Harford Duracool Installation Specifications



**Harford**

## **Work Included:**

- Erect panels in a professional manner.
- Set self-contained refrigeration system and hang coil.
- Set remote condensing unit and hang coil (up to 2 HP only; larger units require a mechanical lift).
- Note: walk-in box installation is based on **ground level**, in a clear area with a smooth level pad.
- Install glass display doors and frames (door adjustment and shelving installation by others.)

*Installation may not be available to meet our Five(5)/Ten(10) Day Win Program commitment. Check with your salesperson.*

## **Work Not Included:**

- Electrical work.
- Condensate drains.
- Placing of condensing units requiring a crane.
- Permits.
- Field piping of refrigeration systems.
- Penetrations through existing building walls.
- Roof cap flashing to existing building.
- Refrigeration start-up.

**If is strongly recommended that a representative of your organization be present during installation.**

**Installation is non-union.**

**Contact office for “prevailing wage” rates.**

## **High-Quality Walk-ins**

*Walk-in Coolers & Freezers • Refrigeration Systems • Refrigerated Warehouses*

HARFORD DURACOOl LLC 2129 Pulaski Hwy, P.O. Box 1026, Aberdeen, MD 21001, USA  
Ph: 800-638-7620 • Fax: 410-272-8508 Visit us online at [www.harfordduracool.com](http://www.harfordduracool.com)

©2004 Harford 2684 - 2/04 Continuing product improvement may necessitate change of specifications without notice.

